

LEGACY POINTE AT WAUKEE PLAT 7 FINAL PLAT

GENERAL NOTES:

1. ALL EASEMENTS SHALL BE PUBLIC UNLESS OTHERWISE NOTED AS PRIVATE.
2. SPOT GRADES NOTED ON THIS PLAN ARE FOR REFERENCE ONLY. SEE CONSTRUCTION DRAWINGS ON FILE AT CITY HALL FOR COMPLETE GRADING INFORMATION.
3. THE MINIMUM OPENING ELEVATIONS (MOE) AND SINGLE SPOT GRADE CALL OUTS ARE IN ACCORDANCE WITH THE STORM WATER MANAGEMENT AND CONSTRUCTION PLANS. THE CITY OF WAUKEE REQUIRES MOE'S AND SPOT GRADES TO BE PLACED ON THE FINAL PLAT. THE SURVEYOR DOES NOT CERTIFY TO THOSE ELEVATIONS SHOWN ON THE PLAT.

MINIMUM OPENING ELEVATION NOTES:

1. MINIMUM PROTECTION ELEVATIONS (MOE) ARE FOR REFERENCE ONLY. ALL LOTS, WITH OR WITHOUT MOE'S, SHALL BE REVIEWED FOR CONFORMANCE WITH THE STORMWATER MANAGEMENT PLAN AND GRADING PLAN.
2. THE HOME BUILDER SHALL ENSURE ALL DRAINAGE SWALES ARE MAINTAINED AND/OR PROTECTED AS DESIGNED DURING HOME CONSTRUCTION AS INTENDED IN THE ORIGINAL DESIGN AND APPROVED BY THE CITY.
3. HOME BUILDERS SHALL BE RESPONSIBLE FOR ENSURING POSITIVE DRAINAGE AWAY FROM HOUSE AND THAT ALL DRAINAGE SWALES AROUND HOUSE ARE SIZED TO CONVEY THE 100-YEAR STORM EVENT. MOE'S LISTED DO NOT ACCOUNT FOR DRAINAGE THROUGH SIDE YARDS INCLUDING THE OVERTOPPING OF STREET LOW POINTS. THE HOME BUILDER SHALL BE RESPONSIBLE FOR GRADING THE SIDE YARD TO ACCOUNT FOR THE VARYING DEPTH OF FLOW AND ENSURING FLOOD PROTECTION AND POSITIVE DRAINAGE AWAY FROM THE HOUSE.
5. MOE'S PROVIDED ARE BASED ON PROPOSED CONTOURS AND NOT ACTUAL AS-BUILT GRADES. HOME BUILDERS MUST ADJUST MOE'S ACCORDINGLY AND GRADE LOT TO HAVE POSITIVE DRAINAGE TO PROPERTY LINES AND PUBLIC WAYS.
6. MOE'S LISTED DO NOT ACCOUNT FOR DEPTH OF SANITARY SERVICE. THE HOME BUILDER SHALL BE RESPONSIBLE FOR VERIFYING THE DEPTH OF THE SERVICES AND SET THE BASEMENT ELEVATION ACCORDINGLY.

PROPERTY DESCRIPTION:

AN OFFICIAL RE-PLAT OF LOTS 3, 4, AND 5, LEGACY POINTE AT WAUKEE PLAT 1, AN OFFICIAL PLAT, ALL INCLUDED IN AND FORMING A PART OF THE CITY OF WAUKEE, DALLAS COUNTY, IOWA.

SAID TRACT OF LAND CONTAINS 2.93 ACRES MORE OR LESS.

SAID TRACT OF LAND BEING SUBJECT TO AND TOGETHER WITH ANY AND ALL EASEMENTS OF RECORD.

ADDRESS:
1595 SE GOLDEN HARVEST DR.
WAUKEE, IA 50263

OWNER:
URBAN FAMILY INVESTMENT LLC
4800 MILLS CIVIC PKWY.
SUITE 205
WEST DES MOINES, IA 50266


PREPARED FOR:
URBAN FAMILY INVESTMENT LLC
4800 MILLS CIVIC PKWY.
SUITE 205
WEST DES MOINES, IA 50266
ATTN: TIM URBAN
PHONE: 515-208-4591

ENGINEER/SURVEYOR:
BISHOP ENGINEERING
ATTN: CHARLES BISHOP
3501 104TH ST
URBANDALE, IA 50322
PH: (515) 278-0467

ZONING
PLANNED DEVELOPMENT DISTRICT PD-C1-A

BULK REGULATIONS:

- DENSITY: TWELVE (12) DWELLING UNITS/ACRE MAXIMUM
- MINIMUM FLOOR AREA: ELEVEN HUNDRED (1,100) S.F. PER UNIT
- MINIMUM LOT WIDTH: TWENTY FOUR (24) FEET
- FRONT YARD SETBACK: TWENTY (20) FEET MINIMUM FROM PUBLIC STREET OR FROM EDGE OF CURB OF A PRIVATE
- REAR YARD SETBACK: TWENTY (20) FEET MINIMUM EXCEPT FOR THOSE UNITS THAT BACK UP TO THE EXISTING DETENTION POND (LOT B OF LEGACY POINTE AT WAUKEE PLAT 1). THE MINIMUM REAR YARD SETBACK SHALL BE TEN (10) FEET
- SIDE YARD SETBACK: TEN (10) FEET MINIMUM BETWEEN PRINCIPAL BUILDINGS
- MAXIMUM NO. OF STORES: TWO (2) STORES
- NUMBER OF CONNECTED UNITS: MAXIMUM OF TWO (2) UNITS
- OFF-STREET PARKING: TWO (2) PARKING STALLS PER UNIT OF WHICH ONE (1) MINIMUM WILL BE IN AN ATTACHED GARAGE. ONE ADDITIONAL STALL FOR EVERY FOUR (4) UNITS FOR VISITOR PARKING
- MINIMUM OPEN SPACE: THE TOTAL LAND AREA DEVOTED TO OPEN SPACE AND LANDSCAPING SHALL NOT BE LESS THAN TWENTY (20%) PERCENT OF THE GROSS LAND AREA CALCULATED AS A WHOLE. INDIVIDUAL LOTS MAY HAVE LESS THAN 20%.



FINAL PLAT
APPROVED BY *City Council*
DATE *04/18/2016*
SIGNED *William P. Givens*

LEGEND:

- △ SECTION CORNER- FOUND AS NOTED
- PROPERTY CORNER- 3/4" IRON PIPE WITH YELLOW PLASTIC CAP ID #14416 OR FOUND AS NOTED
- SET 3/4" IRON PIPE WITH YELLOW PLASTIC CAP ID #14775
- M MEASURED DISTANCE
- P PLATTED DISTANCE
- R RECORDED DISTANCE
- P.R.A. PREVIOUSLY RECORDED AS
- R.O.W. RIGHT-OF-WAY
- P.O.C. POINT OF COMMENCEMENT
- P.O.B. POINT OF BEGINNING
- Y.P.C. YELLOW PLASTIC CAP
- MOE MINIMUM OPENING ELEVATION
- MSE MINIMUM BASEMENT ELEVATION
- MSS MINIMUM GRADE AT STRUCTURE
- ||||| STREET ADDRESS
- 1000.00 SWALE GRADE

ABBREVIATIONS:

- AC ACRES
- BK BOOK
- EX EXISTING
- PG PAGE
- POB POINT OF BEGINNING
- POC POINT OF COMMENCEMENT
- PRA PREVIOUSLY RECORDED AS
- PUE PUBLIC UTILITY EASEMENT
- ROW RIGHT OF WAY
- SF SQUARE FEET
- SAW SANITARY
- TYP TYPICAL
- N NORTH
- S SOUTH
- E EAST
- W WEST

PLAT NOTES:

1. PRIVATE STORM SEWERS SHALL BE MAINTAINED BY THE HOMEOWNERS ASSOCIATION.
2. NO SINGLE FAMILY DRIVEWAYS ARE TO BE LOCATED DIRECTLY TO SE LEGACY POINTE BOULEVARD.
3. ALL LOT CORNERS WILL BE SET WITH IRON PIPE WITHIN ONE YEAR OF RECORDING. ALL SET PIPE WILL BE MARKED WITH YELLOW PLASTIC IDENTIFICATION CAPS (#14775).
4. THIS PLAT HAS AN ERROR OF CLOSURE OF LESS THAN 1.0 FEET IN 10,000 FEET. EACH LOT HAS AN ERROR OF CLOSURE OF LESS THAN 1.0 FEET IN 5,000 FEET.
5. ALL BEARINGS ARE BASED ON AN ASSUMED MERIDIAN FOR COMPUTATION PURPOSES.
6. ALL SIDEWALKS SHALL BE INSTALLED WITH EACH INDIVIDUAL LOT DEVELOPMENT.

BENCH MARK:

1. TOP OF OPERATING NUT ON FIRE HYDRANT LOCATED ON SOUTHEAST PORTION OF LOT 3, LEGACY POINTE AT WAUKEE PLAT 1, ELEVATION = 1017.51

COPYRIGHT 2015 BISHOP ENGINEERING. THIS DOCUMENT AND THE INFORMATION CONTAINED MAY NOT BE REPRODUCED OR EXCERPTED WITHOUT THE EXPRESS WRITTEN PERMISSION OF BISHOP ENGINEERING. UNAUTHORIZED COPYING OR DISCLOSURE OF CONSTRUCTION USE ARE PROHIBITED BY COPYRIGHT LAW.



I HEREBY CERTIFY THAT THIS LAND SURVEYING DOCUMENT WAS PREPARED AND THE RELATED SURVEY WORK WAS PERFORMED BY ME OR UNDER MY DIRECT PERSONAL SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LAND SURVEYOR UNDER THE LAWS OF THE STATE OF IOWA.

SIGNED: *Larry D. Hiler* DATE: *6-17-2016*

LARRY D. HILER, P.L.S., 14775
LICENSE RENEWAL DATE: DEC. 31, 2016
PAGES OR SHEETS COVERED BY THIS SEAL: 1 OF 1

Bishop Engineering
"Planning Your Successful Development"

3501 104th Street
Des Moines, Iowa 50325-3625
Phone: (515) 278-0467 Fax: (515) 278-0417

Established 1959
Civil Engineering & Land Surveying

LEGACY POINTE AT WAUKEE PLAT 7
WAUKEE, IOWA

FINAL PLAT

REFERENCE NUMBER:	150593
DRAWN BY:	GSA
CHECKED BY:	CJB
REVISION DATE:	03-11-16 03-22-16 03-28-16 04-08-16 04-28-16 06-01-16 06-16-16
PROJECT NUMBER:	150593
SHEET NUMBER:	1 OF 1

8/17/2016 2:27:33 PM M:\LAND PROJECTS\2015150593\DWG\FINAL PLAT.DWG

